

**\*\*\*Septic Permit\*\*\***

# SSD-014211

Parcel #: RP03N180085420

<p align="center"><b>Property Location</b></p> <p>Street Address: 114 MAGIC MOUNTAIN RD HAILEY ID 83333</p>	<p align="center"><b>Owner Information</b></p> <p>Land Owner Name: WINDY HILL HAVEN LLC</p> <p>Address: 133 STONEGATE ROAD PORTOLA VALLEY CA 94029 United States</p>
<p><b>Utilization</b></p> <p>New Subsurface Sewage Permit</p>	

**Permit Requirements**

Type of System: Complex engineered	4	Bedrooms
System Type 1: Extra Drainrock	360	Gallons Per Day
System Type 2:	Soil Type: A-2a	USDA
Water Supply: Private	The minimum septic tank capacity is: 1000 gal tank w/500 gal pu	
Water Source: Well	The minimum effective drainfield absorption area is: 360 Square Feet	
	Maximum depth of drainfield installation: 4 feet into native soil	
	Minimum setback from drainfield to surface water: 300 feet	

**Conditions of Approval**

Inspection required before cover  
48 Hours advanced notice required for inspection

**Engineered Systems:**

Carefully review and install according to engineering requirements.  
Changes to engineered plans provided must be reviewed prior to septic installation.  
If soil conditions are encountered other than stated in engineering call SCPHD for new test hole.

**All Systems:**


If soil conditions differ from test hole when installing tank/drainfield, contact SCPHD before installation.  
Confirm all surrounding well locations.  
Changes to structure floorplans must be submitted to SCPHD and approved prior to septic installation.  
Modifications to an already approved plot plan must be submitted and approved prior to septic system installation.

**Additional Conditions:**

System will service a 2 bedroom cabin and a 2 bedroom bunkhouse.  
Engineered design is for extra drainrock trench. Excavation depth is 48 inches. 30 inches of drainrock under pipe is required. 40 lineal feet of 6 foot wide extra drainrock trench is needed.

**Permit Approved By:** Scott Arrell

  
DATE: 01/03/2023



**PERMIT EXPIRES TWO YEARS FROM DATE OF ISSUE**

**Note: (Final approval of this permit requires inspection of the uncovered system.)**

This permit expires if the system is not constructed as approved within two years from the date issued. Once the system is constructed and approved by the Health District, all requirements of the approved plans and specifications, permit and permit application (including operations, maintenance, monitoring, and reporting) are applicable indefinitely and convey through transfer of