

109 Lemhi Drive

BURKS RESIDENCE

Community Drainfield Assessment

The project strongly feels that this is not an option as the sewer line cannot be bored straight down as it needs flatter spots in the line to slow water and effluent. If the flatter spots in the sewer pipe are not provided then all the fluids will out flow the solids and the lines will constantly get plugged.

Secondly, in further research it was brought to the Burks attention that the community drainfield system could possibly be close to its full capacity. This creates a critical uncertainty that the Burks do not want to even consider.

As a final point, the projects proposed septic system is to be installed on already disturbed area of fill and any other option would just create more disturbance.

